



DECEMBER 2023

BEATRIX TAILINGS STORAGE FACILITY (TSF) 2

DETAILS OF TAILINGS STORAGE FACILITY

| | |
|--|--|
| Tailings Storage Facility (TSF) Name | Beatrix TSF 2 (BTX2) |
| Operation | Beatrix |
| Operational Status | Active |
| Operating Segment | RSA - Gold |
| Location | 30 km south of Welkom, Free State – please refer to Figure 1 |
| Latitude, Longitude (decimals) | -28.2736972, 26.7716583 |
| Ore Source | Underground |
| Type of Storage Facility | Impoundment (upstream development) |
| Deposition Methodology | Day-Wall Paddock |
| Year of Commissioning | 2002 |
| Consequence Classification (GISTM, 2020) | Extreme |
| Operating Contractor | Stefanutti Stocks Inland (SSI) |
| Engineer of Record (EoR) | Knight Piesold (Pty) Ltd (KP) |
| Current Maximum Height (m) | 25 |
| Final Maximum Height (m) | 30 |
| Maximum Storage Capacity (tons/month) | 240 000 |
| Total Volume Already Deposited (Mm³) | 28,8 |
| Life of TSF (year) | 2029 @ 1,5m/year |



INNOVATION



COMMITMENT



ACCOUNTABILITY



RESPECT



ENABLING



SAFETY

TECHNICAL ASPECTS:

Design Criteria

GISTM and best practice guidelines including Australian National Committee on Large Dams (ANCOLD) (Guidelines on Tailings Dams, July 2019). Site specific design criteria were specified by the EoR. Details are included in the Design Basis Report (DBR).

Stability Assessment and Mitigation Measures

A detailed stability assessment based on piezocone probing and laboratory test work was conducted in 2022 (KP Reference: RI301-00840/06 Rev 0, 13 April 2022). The assessment indicated unacceptable FoS requiring mitigation measures.

Construction of a buttress in the north-west flank to improve stability and intercept seepage was completed in May 2022 and will be assessed for recommended raise in 2023/2024. Additional vibrating wire piezometers (VWP's) have been installed to enhance monitoring.

Additional piezocone testing and shear vanes tests were undertaken between November 2022 and January 2023 to calibrate the stability assessment results. A refined assessment will be available in Q4 2023 following the results from the laboratory testing.

Dam Breach Assessment

Assessment completed in 2022
(KP Reference: PR301-00726/18 Rev 0, 12 April 2022)

Area of Inundation

Has been identified by EoRs – please refer to Figures 2 & 3

Summary of Human Exposure

Consequence classification has been based on Population at Risk (PAR). Farmers have been identified and are being engaged through various means.

DOCUMENTATION:

Site Specific OMS Manual

Version 2022 available
Mandatory Code of Practice (MCOP) document No: 2.3.A-COP is in place (dated June 2019)

Design Basis Report (DBR)

Version 2023 available
(KP Reference: 301-00726/05 Rev C, 27 July 2023)



INNOVATION



COMMITMENT



ACCOUNTABILITY



RESPECT



ENABLING



SAFETY

Environmental Management System

The Environmental Management System is ISO accredited (ISO 14001:2015)

The initial Environmental Management Programme (EMPr) is dated 2004. Numerous addendums have been submitted with the latest being in 2013.

Surveillance:

Surveillance Frequency

Daily by the Operator and monthly reports of critical controls submitted to and reviewed by the EoR

Surveillance Technology/System

K2Fly Decipher

Deformation Monitoring

Interferometric Synthetic Aperture Radar (InSAR)

Phreatic Surface Levels & Pore Pressure Measurements

Standpipe piezometers
AquaSense Retrofit piezometers (IoT device)
Vibrating Wire Piezometers (VWP's)

RISK MANAGEMENT / EMERGENCY PREPAREDNESS:

Risk Assessment

Annual Risk Assessment (Failure Mode Effect Analysis and Bowtie) completed with no untoward risk identified

Risk Management

Site specific OMS Manual in place
Site specific Trigger Action Response Plans (TARPs) in place
Critical controls established and implemented

Site Specific Emergency Preparedness & Response Plans (EPRP)

Version 2023 available

Annual emergency mock drill for a catastrophic TSF failure – undertaken on 30 June 2023 with SSW employees and contractors.

Environmental emergency preparedness is managed on site according to ISO14001: 2015.



INNOVATION



COMMITMENT



ACCOUNTABILITY



RESPECT



ENABLING



SAFETY

CLOSURE & POST CLOSURE

Closure Planning

In place - report prepared by Golder Associates
(Golder Reference: 20353619-341344-2, April 2021)

Closure Costing

Adequate financial capacity in place
Financials prepared by Golder Associates
(Golder Reference: 20447293-349381-4, December 2021)

Asset Insurance Cover

In place – July 2023 to June 2024

Independent Reviews:

Independent Tailings Review Board (ITRB)

14 July 2022 with no material concerns identified

Future ITRB Review

2024

Performance Reviews

Annual and quarterly reports with inspections completed
by EoR
(KP Reference: RI301-00726/05 Rev A, 23 June 2023)

Dam Safety Review (DSR)

Carried out by an independent third party in 2019/2020
with no material findings.
(KP Reference: 301-00840/02-009 Rev 1, February 2020)

Next review scheduled for 2024



INNOVATION



COMMITMENT



ACCOUNTABILITY



RESPECT



ENABLING



SAFETY




Figure 1: Layout of Beatrix Mine Complex




Figure 2: Consolidated view of the rainy-day failure scenario inundation boundaries




Figure 3: Consolidated view of the sunny-day failure scenario inundation boundaries