

JULY 2023

ORYX (BTX4) TAILINGS
 STORAGE FACILITY (TSF)

DETAILS OF TAILINGS STORAGE FACILITY

Tailings Storage Facility (TSF) Name	Oryx TSF (BTX4)
Operation	Beatrix
Operational Status	Dormant since mid-2019
Operating Segment	RSA - Gold
Location	Approximately 32 km south-west of the town of Virginia in the Free State Province – please refer to Figure 1
Latitude, Longitude (decimals)	-28.188975, 26.7037361
Ore Source	Underground
Type of Storage Facility	Impoundment (upstream development)
Deposition Methodology	Day-Wall Paddock
Year of Commissioning	1981
Consequence Classification (GISTM, 2020)	Significant
Operating Contractor	Stefanutti Stocks Inland (SSI)
Engineer of Record (EoR)	Knight Piesold (Pty) Ltd (KP)
Current Maximum Height (m)	20
Final Maximum Height (m)	20
Total Volume Already Deposited (Mm³)	14,5
Life of TSF (year)	N/A



INNOVATION



COMMITMENT



ACCOUNTABILITY



RESPECT



ENABLING



SAFETY

TECHNICAL ASPECTS:

Design Criteria

GISTM and best practice guidelines including Australian National Committee on Large Dams (ANCOLD) (Guidelines on Tailings Dams, July 2019). Site specific design criteria were specified by the EoR. Details are included in the Design Basis Report (DBR).

Stability Assessment and Mitigation Measures

A detailed stability assessment based on piezocone probing and some laboratory test work was conducted in 2023 (KP Reference: PR301-00726/36-A Rev A, 3 July 2023).

All the FoS are above the recommended limits and thus no mitigation measures were required.

Construction of a buttress in the west flank due to a localised slip was completed in 2001.

Dam Breach Assessment

Assessment completed in 2023
 (KP Reference: PR301-00726/36-A-PR23-00154 Rev 0, 28 July 2023)

Area of Inundation

Has been identified by EoRs – please refer to Figure 2

Summary of Human Exposure

Consequence classification has been based on Population at Risk (PAR). Farmers have been identified and are being engaged through various means.

DOCUMENTATION:

Site Specific OMS Manual

Version 2023 available
 Mandatory Code of Practice (MCOP) document No: 2.3.A-COP is in place (dated June 2019)

Design Basis Report (DBR)

Version 2023 available
 (KP Reference: RI301-00726/36 Rev A, 27 July 2023)

Environmental Management System

The Environmental Management System is ISO accredited (ISO 14001:2015)

The initial Environmental Management Programme (EMPr) is dated 2004. Numerous addendums have been submitted with the latest being in 2013.



INNOVATION



COMMITMENT



ACCOUNTABILITY



RESPECT



ENABLING



SAFETY

Surveillance:

Surveillance Frequency

Daily by the Operator and quarterly reports of critical controls submitted to and reviewed by the EoR

Surveillance Technology/System

K2Fly Decipher

Deformation Monitoring

Interferometric Synthetic Aperture Radar (InSAR)

Phreatic Surface Levels & Pore Pressure Measurements

Standpipe piezometers

RISK MANAGEMENT / EMERGENCY PREPAREDNESS:

Risk Assessment

Annual Risk Assessment (FMEA) completed with no untoward risk identified

Risk Management

Site specific OMS Manual
 Site specific Trigger Action Response Plans (TARPs) in place
 Critical controls established and implemented

Site Specific Emergency Preparedness & Response Plans (EPRP)

Version 2023 available

Annual emergency mock drill for a catastrophic TSF failure – undertaken on 30 June 2023 with SSW employees and contractors.

Environmental emergency preparedness is managed on site according to ISO14001: 2015.

CLOSURE & POST CLOSURE

Closure Planning

In place - report prepared by Golder Associates (Golder Reference: 20353619-341344-2, April 2021)

Closure Costing

Adequate financial capacity in place
 Financials prepared by Golder Associates (Golder Reference: 20447293-349381-4, December 2021)

Asset Insurance Cover

In place – July 2022 to June 2023 (currently undergoing the renewal process)



INNOVATION



COMMITMENT



ACCOUNTABILITY



RESPECT



ENABLING



SAFETY

Independent Reviews:

Independent Tailings Review Board (ITRB)	4 July 2023 with no material concerns identified
Future ITRB Review	2024
Performance Reviews	Annual and quarterly reports with inspections completed by EoR (KP Reference: RI301-00726/38 Rev 0, 3 May 2023)
Dam Safety Review (DSR)	Carried out by an independent third party in 2019/2020 with no material findings (KP Reference: 301-00840/02-010 Rev 1, February 2020) Next review scheduled for 2024






Figure 1: Layout of Oryx TSF




Figure 2: Consolidated View of Rainy-Day Scenarios Area of Inundations